KADUR DIVISION.

Notice dated 10th March 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 10th April 1928, till 2 P.M., for constructing a new tank across Bekkinahalla Lingadahalli Hobli, Tarikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit	
		In figures	In words

4. Each tender must be accompanied by a deposit of Rs. 1,500 (one thousand and five hundred only in cash or Government Promissory Notes, or Post Office Certificate or State Loan Bonds at market rate or in Savings Bank Pass Book having that amount at the credit of the tenderer on that date as earnest money, and be superscribed. "Tender for constructing a new tank across Bekkinahalla", in default of which, tenders will be rejected.

5. The final acceptance of this tender will rest with the Government who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. No claims for enhanced rates will be permitted during the execution of the work.

10. The rates should be noted both in figures and words without any change in the items of work.

11. In all matters of dispute regarding quality and quantities of work the decision of the Chief Engineer is final and legally binding.

Approximate quantity for constructing a new tank across Bekkinahalla, Tarikere Taluk.

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
1	Earthwork removing aluvial deposit from valley on bund line and spoil used to rear slope of bund.	C.yd.	10,069		
2	Earthwork cutting trenches and using spoil to rear slope of bund.	,,	1,235		
3	Earthwork forming seat and spoil to rear slope of bund.	,,	2,304		
4	Earthwork cutting trench for constructing puddle wall and using spoil to rear slope of bund.	,,	1,614		
5	Constructing puddle wall with watering and tamping.	,,	5,501		
6	Earthwork to bund by pits including watering and tamping.	,,	59,946		
7	Rough stone work revetment including jelly backing and wedging and lead of average 1½ miles.	,,	8,913		
8	Gravel backing to revetment	,,	2,219		

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
9	Turfing inclusive of watering and rammering.	S.yd.	12,195		
10	Grade stone inclusive of cutting figures painting with white lead and numbering with Japan and fixing over bed slab.	No.	29		
11	Vesuvis stone as per type design ...	„	29		
12	Registered No. stone including cutting figures and letters and painting with white lead and numbering with Japan.	„	...		
13	Gauge stone inclusive of neat chisselling marking graduation and painting with white lead and numbering with Japan and fixing over bed slab.	„	4		
14	Removing tamarind tree and jungle clearing on bund line.	Lump sum			
15	B. M. stone inclusive of cutting figures painting with white lead and numbering with Japan and fixing on concrete bed.	No.	2		
16	Earthwork carted from weir site and used to bund including lead.	C.yd.	6,931		
17	Earthwork stoney gravelly soil excavation	„	10,246		
18	Removing soft rock	„	209		
19	Concrete in surki mortar	C.ft.	899		
20	Burnt brick in surki mortar	„	5,428		
21	Burnt stone slabs neatly dressed and fixed in mortar. (8″ to 9″).	S.ft.	247		
22	New rough stone work apron and revetment.	C.yd.	491		
23	Jelly filling beneath apron	„	470		
24	Rough stone in surki mortar	C.ft.	1,286		
25	Providing pin stones to coping slabs ...	No.	9		
26	Plastering with surki mortar	Sqr.	16·50		
27	Earthwork excavation ordinary soil and forming spoil bank.	C.yd.	1,965		
28	Earthwork excavation gravelly soil and forming spoil bank.	„	3,038		
29	Lifting dam at site where weir channel crosses irrigation channel.	Lump sum			
30	Earthwork embankment including watering and tamping.	C.yd.	2,420		
31	Burnt stone slabs flooring 4″ thick set in mortar and cement pointing.	S.ft.	369		
32	Cast iron pipe 12 diameter inclusive of carting to work site and railway freight and fixing in cement.	Cwt.	42·95		
33	Gear rod hexagonal unit box teak plug, etc.	Lump sum			
34	Boring holes in guide slab and upper and lower orifice slab.	No.	5		
35	Fixing cast iron pipe lead joint ...	„	4		
36	Plastering with cement and making guage to weir level.	R.ft.	25		
37	Pipe of 6″ diameter aqueduct to lead channel water across Barahalla for minor irrigation fixing stone posts.	„	200		
38	Constructing rough stone way tunnels across right and left channels on bund and other items.	No.	3		

Notice Dated 10th March 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division Chikmagalore, up to 4th April 1928, till 2 P.M., for constructing combined Dispensary and Inpatient Ward and Quarters at Tarikere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalore between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit	
		In figures	In words

4. Each tender must be accompanied by a deposit of Rupees four-hundred and fifty (Rs. 450) only in cash or Post Office cash certificates or State Loan bands at market rates in cash or Government Promissiory Notes, as earnest money, and be superscribed "Tender for constructing combined Dispensary and Inpatient Ward and Quarters at Tarikere, in default of which tenders will be rejected.

5. The final acceptance of this tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures without any correction.

10. The contractor will not be allowed to claim enhanced rates after submission of tender at any stage.

11. The decision of the Chief Engineer will be final and legally binding on the contractor in case of disputes about the rates, qualities and quantities of work.

Approximate quantity for constructing a combined Dispensary and Inpatient Ward at Tarikere, Kadur District.

(Quantity for main building, Kitchen and Latrine.)

No.	Items of work	Per	Quantity	Rates tendered	
				In figures	In words
				Rs. a. p.	Rs.
1	Earthwork excavation and filling in basement including watering and tamping.	C.yd.	243		
2	Stone jelly concrete in mortar foundation ...	C.ft.	2,520		
3	Burnt stone in mortar	,,	4,247		
4	Burnt brick in mortar	,,	5,740		
5	Burnt brick in mortar arch work ...	,,	1284		
6	Burnt stone slabs roughly dressed ...	S.ft.	411		
7	Teakwood work wrought and put up ...	C.ft.	209·74		

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	Rs.
8	Providing and fixing H. iron steel joists in compounding room including Railway freight, carriage, etc.	Cwt.	5		
9	Cut stone pillars 9″ x 9″ nicely dressed including capitals and base.	No.	7		
10	Constructing masonry half pillar at the ends with base and capitals.	R.ft.	16		
11	Teakwood doors panelled including hinges screws, bolts, nuts, etc., complete.	S.ft.	456		
12	Teakwood windows with rectangular glazed ventilators at top, half panelled and half glazed shutters in side hinges, bolts, hooks, rings, etc., complete.	,,	48		
13	Teak windows with half panelled and half glazed shutters inside with ¼″ iron bar, crossed bar hinges, bolts, hooks, rings etc., complete.	,,	236		
13 (a)	Teakwood windows with panelled shutters inside ¾″ dia. iron bar expanded metal outside, hinges, clamps, etc.	,,	12		
14	Teakwood ventilators with glazed shutters and expanded metal iron bars, etc., complete.	,,	14		
15	Circular ventilators with glazed shutters with cotton rope, etc.	,,	9·43		
16	Providing teakwood wall-shelves with panelled shutters, planks, hinges, bolts, locks, etc., complete.	,,	95		
17	Roofing with 1st class Mangalore tiles on teak reepers nailed, etc., complete.	Sqr.	40·13		
18	Ridge tiles set in mortar and cement pointing, etc., complete.	R.ft.	196		
19	Flooring with square Mangalore tiles on 3″ concrete bed and cement pointing.	Sqr.	15·43		
20	Flooring with Cuddappa slab on 3″ concrete bed and cement pointing.	,,	5·37		
20 (a)	Flooring with burnt stone slabs with 3″ concrete bed and cement pointing.	,,	0·50		
21	Plastering with chunam mortar ...	,,	113·75		
22	Cement pointing	,,	6·43		
23	Providing wooden partition with ½″ thick plank and necessary adjustment, etc.	S.ft.	210		
24	White and colour washing	Sqr.	113·75		
25	Silicate chocolate painting 2 coats ...	,,	15·76		
26	Wood oiling 2 coats	,,	18·60		
27	Providing and fixing teakwood eave board ornamental 9″ x 1″.	R.ft.	426		
28	Do do ordinary	,,	61		
29	Providing and fixing teak barge board ornamental, etc., complete.	S.ft.	40		
30	Constructing lead off drains ...	Lump sum			
31	Providing teakwood planking for valleys ...	S.ft.	188		
32	Providing zinc sheet gutters for the valleys	,,	188		
33	Constructing sinks in bath rooms with 4½″ up-right slabs with flooring in surki concrete bed and 2′ Galvanised pipe fixing in cement.	No.	3		

Serial No.	Items of work	Per	Quantity	Rates tendered	
				In figures	In words
				Rs. a. p.	
34	Providing and fixing ornamental finials and pendents	No.	28		
35	Cement colour washing to basement ...	Sqr.	6·43		
36	Constructing chunam borders	R.ft.	236		
37	Whitelead painting to the steel joists ...	Sqr.	0·44		
38	Providing Cuddappa slab flooring 2" thick and edges rounded	,,	0·64		
39	Decorating front big windows	Lump sum			
40	Constructing an oven in the kitchen ...	Lump sum			
41	Providing and fixing mortar and pestle stone in the kitchen	Lump sum			
42	Providing and fixing ventilating tiles in chimneys	Lump sum			
43	Constructing coping including plastering ...	R.ft.	38		
44	Cut stone seats fixed in cement ...	Lump sum			
45	Tarring two coats	Sqr	1·17		
46	Clearing site and levelling ground ...	Lump sum			
47	Date and year stone with inscription, etc. ...	Lump sum			

Approximate quantity for constructing a labour ward attached to combined Dispensary at Tarikere, Kadur District.

1	Earthwork excavation and filling in basement including watering and tamping.	C.yd.	70		
2	Stone jelly concrete	C.ft.	721		
3	Burnt stone in mortar for foundation and basement	,,	1,180		
4	Burnt brick in mortar, superstructure ...	,,	1,771		
5	Burnt stone slabs 4½" to 6" thick roughly dressed and fixed	S.ft.	169		
6	Teakwood wrought and put up including wood oiling	C.ft.	65·41		
7	Teakwood door half panelled and half glazed, etc.	S.ft.	105		
8	Teakwood windows with 4 half shutters bottom panelled top glazed with 1" bars, etc., complete	,,	150		
9	Teak glazed ventilators with expanded metal	,,	54		
10	Roofing with 1st Class Mangalore tiles on Teak reepers, etc.	Sqr.	11·96		
11	Mangalore ridge tiles set in mortar and cement pointed	R.ft.	84		
12	Flooring with 1st Class Mangalore Square tiles on 3" concrete bed and cement pointing	Sqr.	4·94		
13	Plastering with chunam	,,	33·78		
14	White and colour washing 2 coats ...	,,	33·78		
15	Cement pointing to basement	,,	2·30		
16	Cement plastering ½" thick	,,	1·32		
17	Silicate chocolate painting 2-coats ...	,,	5·81		
18	Wood oiling 2 coats	,,	1·99		
19	Teakwood ornamental eave board 9" × 1"	R.ft.	126		
20	Do do 6" × 1"	,,	139		
21	Masonry finials (tiles).	No.	2		
22	Teakwood pendents, big	,,	4		
23	Providing a sink in bath room with burnt stone upright and champered, etc., burnt stone flooring on 3" concrete and cement pointing and galvanized iron pipe outlet and a masonry cistern outside 3' × 3' × 2'	,,	1		
24	Teakwood pendents, small	,,	24		

Serial No.	Items of work	Per	Quantity	Rates tendered	
				In figures	In words
	Approximate quantity for constructing quarters for Lady Sub-Assistant Surgeon, at Tarikere.				
				Rs. a. p.	
1	Earthwork excavation and filling in ...	C.yd.	36		
2	Stone in clay foundation and basement ...	C.ft.	1,497		
3	Burnt brick in clay superstructure ...	„	1,086		
4	Burnt brick in chunam	„	384		
5	Arch work brick in chunam	„	48		
6	Burnt stone slabs 6" thick	S.ft.	119		
7	Teakwood work wrought and put up ..	C.ft.	59·19		
8	Rough plastering with chunam one coat ½" thick well rubbed with trowel and pressed with pebbles from the sand screenings thrown on the surface to get the effect of rough cast work ...	Sqr.	43·20		
9	Teakwood doors frame of 3" × 5" and jungle wood battened shutters with ¾" battens and 1" planks including iron fittings locks, etc., complete ...	S.ft.	144		
10	Teakwood window frame 3" × 4" and junglewood battened shutters of ½" battens and 1" planks with iron fittings, etc., complete	„	36		
11	Teakwood ventilators, glazed shutters, complete	„	30		
12	Roofing with 1st Class Mangalore tiles on teak reepers, nails, etc., complete ...	Sqr.	12·40		
13	Madras terrace	„	80		
14	Parapet wall	R.ft.	24⅓		
15	Cornice, 7" thick	„	25½		
16	Smooth plastering outside to pillars as per design	Lumpsum			
17	Flooring with 1st Class Mangalore tiles on 3" bed pointed with cement ...	Sqr.	2·97		
18	Flooring with Cuddapah slabs on 3" concrete bed pointed with cement ...	„	78		
19	Flooring with chunam or unslaked lime or kankar well watered and tempered and smoothened as in vajragare ...	„	2·08		
20	Ridge tiles set in mortar	R.ft.	112		
21	Junglewood eave board with painting ...	„	189		
22	Pointing to basement	Sqr.	2·88		
23	Coping with burnt brick in chunam and plastering, complete	R.ft.	65		
24	Chocolate painting	Sqr.	4·80		
25	Unforeseen and clearing, gravelling and chimney arrangement and out-let ...	Lumpsum			
26	Mortar and pestle	Lumpsum			

B. R. GARUDACHAR,
Executive Engineer.